



NOTES:

1. AFTER INITIAL EXCAVATION, PLACE AND COMPACT SUITABLE CLAYEY MATERIAL AS SPECIFIED. PROVIDE CRADLE FOR PIPE EQUAL TO SPECIFIED BEDDING CLASS. AFTER PIPE INSTALLATION, PLACE AND COMPACT SUITABLE CLAYEY MATERIAL WITHIN PIPE ENVELOPE TO SPECIFIED DENSITY.
2. ABOVE PIPE ENVELOPE PLACE SUITABLE EXCAVATED MATERIAL AND COMPACT TO DENSITY SPECIFIED FOR TRENCH BACKFILL.
3. CONTRACTOR MAY ELECT TO REEXCAVATE, AFTER INITIAL INSTALLATION AND BACKFILLING, TO CONSTRUCT WATERSTOP. APPROPRIATE MEASURES TO PROTECT PIPE AND TO MAINTAIN ITS SUPPORT, SHALL BE TAKEN.
4. WATERSTOPS SHALL BE SPACED AT NOMINAL 800 FOOT INTERVALS OR AS INDICATED IN THE DRAWINGS.

FILE NO.: 2200-040	CEDAR RAPIDS METROPOLITAN AREA STANDARD DETAILS FOR PUBLIC IMPROVEMENTS		NO. 2200-040
APPROVAL DATE: APRIL 2003			
REVISION NO.:	WATERSTOP FOR TRENCHES		
REVISION DATE:			