

SECTION 01000

SPECIAL PROVISIONS

The Cedar Rapids Metropolitan Area Standard Specifications and Details are applicable to this project. The purpose of this section is to revise, identify, add, and/or clarify conditions relating to specific items on this project.

Modify Cedar Rapids Metro Area Standard Specifications for Public Improvement as follows:

SECTION 01025 – MEASUREMENT AND PAYMENT

ADD 01400-39	REMOVAL AND RELOCATION OF PVC DRAIN PIPE Loading, hauling and disposal of materials in this item and furnishing, relocating, and installing new PVC drains are incidental.
ADD 01400-63	REMOVAL AND SALVAGE OF EXISTING FLANGED PIPE, FITTINGS, AND VALVES Includes removal, short term on-site storage followed by re-use OR disposal by Contractor, whichever is applicable. Capping or plugging and disposal of miscellaneous fittings are incidental.
ADD 02500-02	RE-INSTALLATION OF SALVAGED FLANGED PIPE, FITTINGS, AND VALVES Gaskets, hardware and other materials required for installation are incidental.
ADD 02500-03	FURNISH AND INSTALLATION OF 8-INCH RPZ STANDS Furnishing of materials and installation are incidental.
ADD 02500-04	FURNISH AND INSTALLATION OF 6-INCH VALVE STANDS Furnishing of materials and installation are incidental.
ADD 02500-05	FURNISH AND INSTALLATION OF 4-INCH PIPE CLAMPS Furnishing of materials and installation are incidental.
ADD 02500-22	INSTALLATION OF 8-INCH STRAINER Material supplied by the Owner shall be as indicated in the Contract Documents. Pick-up and delivery of material to the jobsite is incidental.
ADD 02500-23	INSTALLATION OF 8-INCH METER Material supplied by the Owner shall be as indicated in the Contract Documents. Pick-up and delivery of material to the jobsite is incidental.
ADD 02500-32	FURNISH AND INSTALLATION OF 4-INCH DIAMETER FLANGED SPOOL Other piping materials required for installation are incidental.
MODIFY 02500-60	DISINFECTION This item includes furnishing all materials, labor, and equipment to disinfect the water main and re-disinfect if required, of the completed water main. Lump sum price includes installation and removal of temporary hydrants, blowoffs or other fixtures, corporation stops, copper tubing, hoses, pumps, gauges and other equipment required for disinfection. Also included are hoses, piping and accessories necessary to conduct the chlorinated water to a proper disposal point.