



**To:** All Companies Interested in Submitting a Bid  
**From:** Rebecca Johnson, CPPB, Purchasing Agent  
**RFB:** Electrical Service Installation at Noelridge Park (RFB #PUR0318-150);  
Dated: April 6, 2018  
**Subject:** Addendum #1 (1 page)  
**Date:** April 12, 2018

---

The following questions and/or clarifications were asked relative to the above-listed Request for Bid. This memo is sent for clarification to all companies to whom the RFB was sent.

**Updates to Scope of Work following pre-bid meeting held April 11, 2018:**

4.2.1 REVISED / ADD

At the existing electrical service panel, come out the side of the panel to a 2" LB then down to a junction box, then run 1 1/4" conduit to the existing 4" inter-duct. Contractor shall directional bore conduit from the electrical panel to the existing inter-duct.

4.2.2 REVISED

Contractor shall add additional breakers at the existing panel to allow the service to handle the outlets being installed per section 4.2.5 below.

4.2.3 REVISED

At the point where the Contractor ties into the existing inter-duct conduit the Contractor shall install a Hand-hole that is traffic rated to handle 4,000 lbs.

4.2.5 REVISED

At the location of the outlets, the Contractor shall furnish and install two (2) Legrand Outdoor Ground Boxes, one that contains two (2) 20-amp duplex receptacles (item XB814C520BK), and one that contains a single (1) 30-amp 120V receptacle (item XB814CL530BK). Contractor shall install the boxes at existing grade per manufacturer's specifications.

4.2.8 ADDITION

Site Restoration: Contractor shall fine grade and seed all disturbed areas with sunny mix per Cedar Rapids Metro Specifications. Contractor shall place erosion control matting on seeded areas and pin down per manufacturer's specifications.

---

All addenda that you receive shall become a part of the contract documents and shall be acknowledged and dated on the bottom of the Signature Page (Attachment C). The deadline for bid submittal is Thursday, April 19, 2018 before 3:00 p.m. CDT.

---